



Shenzhen CTL Testing Technology Co., Ltd.  
Tel: +86-755-89486194 E-Mail:ctl@ctl-lab.com

### FCC SDoC Test Report

### FCC PART 15 Subpart B

Report Reference No.....: CTL1903042101-F

Compiled by  
( position+printed name+signature)...: File administrators Lykan Cai

Name of the organization performing the tests  
( position+printed name+signature)...: Technique principal Ivan Xie

Approved by  
( position+printed name+signature)...: Manager Tracy Qi



Date of issue.....: Mar. 15, 2019

Representative Laboratory Name ..: Shenzhen CTL Testing Technology Co., Ltd.

Address.....: Floor 1-A, Baisha Technology Park, No.3011, Shahexi Road, Nanshan District, Shenzhen, China 518055

Test Firm.....: Shenzhen CTL Testing Technology Co., Ltd.

Address.....: Floor 1-A, Baisha Technology Park, No.3011, Shahexi Road, Nanshan District, Shenzhen, China 518055

Applicant's name.....: ShenZhen Fiberroad Technology CO., Limited

Address.....: 2F, Building 15, Longbi Industrial Park, Dafa Road, Bantian, Longgang District, 518129, Shenzhen, P.R.China

**Test specification:**

Standard.....: FCC PART 15 Subpart B

TRF Originator.....: Shenzhen CTL Testing Technology Co., Ltd.

Master TRF.....: Dated 2011-01

**Shenzhen CTL Testing Technology Co., Ltd.**

This publication may be reproduced in whole or in part for non-commercial purposes as long as the Shenzhen CTL Testing Technology Co., Ltd. is acknowledged as copyright owner and source of the material. Shenzhen CTL Testing Technology Co., Ltd. takes no responsibility for and will not assume liability for damages resulting from the reader's interpretation of the reproduced material due to its placement and context.

Test item description .....: Industrial Switch

Trade Mark.....: Fiberroad

Test voltage.....: DC 12V

Result.....: Pass

# FCC Test Report

<b>Test Report No. :</b>	<b>CTL1903042101-F</b>	Mar. 15, 2019
		Date of issue

Equipment under Test : Industrial Switch

Type / Model : FR-7M3416

Listed Models : FR-7N1XXX-(P), FR-7N2XXX-(P), FR-7N3XXX-(P), FR-7M1XXX-(P),  
FR-7M2XXX-(P), FR-7M3XXX-(P), FR-7M2XCXX-(P), FR-7M3XCXX-(P)

**Applicant** : **ShenZhen Fiberroad Technology CO., Limited**

Address : 2F, Building 15, Longbi Industrial Park, Dafa Road, Bantian, Longgang District, 518129, Shenzhen, P.R.China

**Manufacturer** : **ShenZhen Fiberroad Technology CO., Limited**

Address : 2F, Building 15, Longbi Industrial Park, Dafa Road, Bantian, Longgang District, 518129, Shenzhen, P.R.China

<b>Test Result</b>	<b>Pass</b>
--------------------	-------------

The test report merely corresponds to the test sample.

It is not permitted to copy extracts of these test result without the written permission of the test laboratory.

## History of this test report

Report No.	Version	Description	Issued Date
CTL1903042101-F	V1.0	Initial Issued Report	Mar. 15, 2019

## Content

<b>1.</b>	<b><u>TEST STANDARDS .....</u></b>	<b><u>5</u></b>
<b>2.</b>	<b><u>SUMMARY .....</u></b>	<b><u>6</u></b>
2.1.	General Remarks	6
2.1.	Equipment Under Test	6
2.1.	Short description of the Equipment under Test (EUT)	6
2.1.	EUT operation mode	6
2.1.	EUT configuration	6
2.1.	Related Submittal(s) / Grant (s)	7
2.1.	Modifications	7
2.1.	Test Result Summary	7
<b>3.</b>	<b><u>TEST ENVIRONMENT .....</u></b>	<b><u>8</u></b>
3.1.	Address of the test laboratory	8
3.2.	Test Facility	8
3.3.	Environmental conditions	8
3.4.	Statement of the measurement uncertainty	9
3.5.	Equipments Used during the Test	9
<b>4</b>	<b><u>TEST CONDITIONS AND RESULTS .....</u></b>	<b><u>10</u></b>
4.1.	Radiated Emission Test	10
<b>5.</b>	<b><u>TEST SETUP PHOTOS OF THE EUT .....</u></b>	<b><u>18</u></b>
<b>6.</b>	<b><u>PHOTOS OF THE EUT .....</u></b>	<b><u>19</u></b>

## **1. TEST STANDARDS**

The tests were performed according to following standards:

[FCC Rules Part 15 Subpart B - Unintentional Radiators](#)

[ANSI C63.4-2014](#)

## **2. SUMMARY**

### **2.1. General Remarks**

Date of receipt of test sample : Mar. 06, 2019

Sampling and Testing commenced on : Mar. 06, 2019

Testing concluded on : Mar. 15, 2019

### **2.1. Equipment Under Test**

#### **Power supply system utilised**

Power supply voltage :  120V / 60 Hz  115V / 60Hz  
 12 V DC  24 V DC  
 Other (specified in blank below)

DC 9V~56V

### **2.1. Short description of the Equipment under Test (EUT)**

The EUT is a Industrial Switch

### **2.1. EUT operation mode**

The EUT has been tested under typical operating condition.

### **2.1. EUT configuration**

**The following peripheral devices and interface cables were connected during the measurement:**

- - supplied by the manufacturer
- - supplied by the lab

## 2.1. Related Submittal(s) / Grant (s)

This test report is intended for Industrial Switch filing to comply with the FCC Part 15, Subpart B Rules.

## 2.1. Modifications

No modifications were implemented to meet testing criteria.

## 2.1. Test Result Summary

Test Item	Test Requirement	Standard Paragraph	Result
Radiated Emission	FCC PART 15 Subpart B	Section 15.109	PASS

### **3. TEST ENVIRONMENT**

#### **3.1. Address of the test laboratory**

Shenzhen CTL Testing Technology Co., Ltd.  
Floor 1-A, Baisha Technology Park, No. 3011, Shahexi Road, Nanshan, Shenzhen 518055 China

#### **3.2. Test Facility**

The test facility is recognized, certified, or accredited by the following organizations:

##### **IC Registration No.: 9618B**

The 3m alternate test site of Shenzhen CTL Testing Technology Co., Ltd. EMC Laboratory has been registered by Certification and Engineer Bureau of Industry Canada for the performance of with Registration No.: 9618B on November 13, 2013.

##### **FCC-Registration No.: 399832**

Shenzhen CTL Testing Technology Co., Ltd. EMC Laboratory has been registered and fully described in a report filed with the (FCC) Federal Communications Commission. The acceptance letter from the FCC is maintained in our files. Registration 399832, December 08, 2017.

Certificated by A2LA, USA  
Registration No.:4343.01  
Date of registration: December 27, 2017

#### **3.3. Environmental conditions**

During the measurement the environmental conditions were within the listed ranges:

Temperature:	<u>15-35 ° C</u>
Humidity:	<u>30-60 %</u>
Atmospheric pressure:	<u>950-1050mbar</u>

### 3.4. Statement of the measurement uncertainty

The data and results referenced in this document are true and accurate. The reader is cautioned that there may be errors within the calibration limits of the equipment and facilities. The measurement uncertainty was calculated for all measurements listed in this test report acc. to CISPR 16 - 4 „Specification for radio disturbance and immunity measuring apparatus and methods – Part 4: Uncertainty in EMC Measurements“ and is documented in the Shenzhen CTL Testing Technology Co., Ltd quality system acc. to DIN EN ISO/IEC 17025. Furthermore, component and process variability of devices similar to that tested may result in additional deviation. The manufacturer has the sole responsibility of continued compliance of the device.

Hereafter the best measurement capability for CTL laboratory is reported:

Test	Range	Measurement Uncertainty	Notes
Radiated Emission(chamber1)	30~1000MHz	± 3.20dB	(1)
Radiated Emission(chamber2)	30~1000MHz	± 3.53dB	(1)
Radiated Emission	Above 1GHz	± 4.32dB	(1)
Conducted Emission	0.15~30MHz	± 2.66dB	(1)
Disturbance Power	30~300MHz	± 2.90dB	(1)

- (1) This uncertainty represents an expanded uncertainty expressed at approximately the 95% confidence level using a coverage factor of k=2.

### 3.5. Equipments Used during the Test

Radiated Emission(Chamber 1) (Below 1GHz)						
Item	Test Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal.Due
1	ULTRA-BROADBAND ANTENNA	Sunol Sciences Corp.	JB1 Antenna	A061713	2018/10/08	2019/10/07
2	EMI Test Receiver	ROHDE & SCHWARZ	ESCI	1166.5950.03	2018/05/25	2019/05/24


Radiated Emission(Chamber 2) (Above 1GHz)						
Test Equipment	Manufacturer	Model No.	Serial No.	Last Cal.	Cal.Due	
EMI Test Receiver	ROHDE & SCHWARZ	ESCI	1166.5950.03	2018/05/25	2019/05/24	
Horn Antenna	Sunol Sciences Corp	DRH-118	A062013	2018/05/25	2019/05/24	

## 4 TEST CONDITIONS AND RESULTS


### 4.1. Radiated Emission Test

#### TEST CONFIGURATION


(A) Radiated Emission Test Set-Up, Frequency Below 30MHz



(B) Radiated Emission Test Set-Up, Frequency below 1000MHz



(C) Radiated Emission Test Set-Up, Frequency above 1000MHz



### Field Strength Calculation

The field strength is calculated by adding the Antenna Factor and Cable Factor and subtracting the Amplifier Gain and Duty Cycle Correction Factor(if any) from the measured reading. The basic equation with a sample calculation is as follows:

$$FS = RA + AF + CL - AG$$

Where FS = Field Strength	CL = Cable Attenuation Factor (Cable Loss)
RA = Reading Amplitude	AG = Amplifier Gain
AF = Antenna Factor	

### RADIATION LIMIT

For unintentional device, according to § 15.109(a), except for Class A digital devices, the field strength of radiated emissions from unintentional radiators at a distance of 3 meters shall not exceed the following values:

Frequency (MHz)	Distance (Meters)	Radiated (dB $\mu$ V/m)	Radiated ( $\mu$ V/m)
30-88	3	50.0	100
88-216	3	53.5	150
216-960	3	56.0	200
Above 960	3	64.0	500
Frequency (MHz)	Distance (Meters)	QP(dB $\mu$ V/m)	AV(dB $\mu$ V/m)
1000 ~ 6000	3	80	60

For intentional device, according to § 15.209(a), the general requirement of field strength of radiated emissions from intentional radiators at a distance of 3 meters shall not exceed the above table.

### Test Procedure

1. The EUT is placed on a turntable, which is 0.8m above ground plane.
2. The turntable shall be rotated for 360 degrees to determine the position of maximum emission level.
3. EUT is set 3m away from the receiving antenna, which is varied from 1m to 4m to find out the highest emissions.
4. Maximum procedure was performed on the six highest emissions to ensure EUT compliance.
5. And also, each emission was to be maximized by changing the polarization of receiving antenna both horizontal and vertical.
6. Repeat above procedures until the measurements for all frequencies are complete.

### Radiation Test Results


**Shenzhen CTL Testing Technology Co., Ltd**

**Radiation Emission Test FCC PART 15**

EUT: FR-7M3416  
 Manufacturer: Shenzhen Fiberroad Technology CO., Limited  
 Operating Condition: WORKING  
 Test Site: Chamber 1  
 Operator: WZ  
 Test Specification: DC 12V  
 Comment: /  
 Start of Test: 13/03/2019 / 23:40:43

**SWEEP TABLE: "test (30M-1G)"**

Short Description: Field Strength  
 Start Stop Detector Meas. IF Transducer  
 Frequency Frequency Time Bandw.  
 30.0 MHz 1.0 GHz MaxPeak 300.0 ms 100 kHz JB1



**MEASUREMENT RESULT: "CTL190313536\_red"**

13/03/2019 23:42

Frequency MHz	Level dBµV/m	Transd dB	Limit dBµV/m	Margin dB	Det.	Height cm	Azimuth deg	Polarization
57.160000	30.80	7.9	50.0	19.2	---	0.0	0.00	HORIZONTAL
171.620000	41.30	14.5	53.5	12.2	---	0.0	0.00	HORIZONTAL
175.500000	43.10	14.6	53.5	10.4	---	0.0	0.00	HORIZONTAL
208.480000	39.20	14.5	53.5	14.3	---	0.0	0.00	HORIZONTAL
249.220000	41.70	14.4	56.0	14.3	---	0.0	0.00	HORIZONTAL
749.740000	43.80	24.9	56.0	12.2	---	0.0	0.00	HORIZONTAL


**Shenzhen CTL Testing Technology Co., Ltd**

**Radiation Emission Test FCC PART 15**

EUT: FR-7M3416  
 Manufacturer: Shenzhen Fiberroad Technology CO., Limited  
 Operating Condition: WORKING  
 Test Site: Chamber 1  
 Operator: WZ  
 Test Specification: DC 12V  
 Comment: /  
 Start of Test: 13/03/2019 / 23:38:33

**SWEEP TABLE: "test (30M-1G)"**

Short Description:		Field Strength			
Start	Stop	Detector	Meas. Time	IF Bandw.	Transducer
30.0 MHz	1.0 GHz	MaxPeak	300.0 ms	100 kHz	JB1




**MEASUREMENT RESULT: "CTL190313535\_red"**

13/03/2019 23:40

Frequency MHz	Level dBµV/m	Transd dB	Limit dBµV/m	Margin dB	Det.	Height cm	Azimuth deg	Polarization
39.700000	43.20	15.2	50.0	6.8	---	0.0	0.00	VERTICAL
86.260000	39.90	8.8	50.0	10.1	---	0.0	0.00	VERTICAL
136.700000	40.80	15.0	53.5	12.7	---	0.0	0.00	VERTICAL
167.740000	41.30	14.5	53.5	12.2	---	0.0	0.00	VERTICAL
212.360000	44.40	14.5	53.5	9.1	---	0.0	0.00	VERTICAL
278.320000	46.70	15.4	56.0	9.3	---	0.0	0.00	VERTICAL

EUT: FR-7MB416  
 Manufacturer: ShenZhen Fiberroad Technology CO., Limit  
 Operating Condition: WAORKING  
 Test Site: Chamber 2  
 Operator: WYC  
 Test Specification: DC12V  
 Comment: /

Data: 1750 File: E:\E3 TEST DATA\1g-6g scan.EM6 (1796) Date: 2019-03-15 Time: 09:21:59




Trace: (Discrete)

Mark	Frequency MHz	Level dBuV	Factor dB	Reading dBuV	Limit dB	Margin dB	Det.	Polarization
1	2000.00	51.87	-4.16	56.03	80.00	28.13	Peak	HORIZONTAL
2	2060.00	51.44	-3.98	55.42	80.00	28.56	Peak	HORIZONTAL
3	2750.00	46.97	-2.11	49.08	80.00	33.03	Peak	HORIZONTAL
4	3315.00	47.03	0.65	46.38	80.00	32.97	Peak	HORIZONTAL
5	3435.00	47.52	0.95	46.57	80.00	32.48	Peak	HORIZONTAL
6	5000.00	57.15	5.43	51.72	80.00	22.85	Peak	HORIZONTAL

EUT: FR-7M3416  
 Manufacturer: ShenZhen Fiberroad Technology CO., Limit  
 Operating Condition: WAORKING  
 Test Site: Chamber 2  
 Operator: WYC  
 Test Specification: DC12V  
 Comment: /

Data: 1751 File: E:\E3 TEST DATA\1g-6g scan.EM6 (1796)




Trace: (Discrete)

Mark	Frequency MHz	Level dBuV	Factor dB	Reading dBuV	Limit dB	Margin dB	Det.	Polarization
1	2000.00	46.38	-4.16	50.54	60.00	13.62	Average	HORIZONTAL
2	2060.00	46.31	-3.98	50.29	60.00	13.69	Average	HORIZONTAL
3	3000.00	41.05	-0.78	41.83	60.00	18.95	Average	HORIZONTAL
4	3310.00	42.07	0.65	41.42	60.00	17.93	Average	HORIZONTAL
5	4000.00	41.90	3.40	38.50	60.00	18.10	Average	HORIZONTAL
6	5000.00	52.93	5.43	47.50	60.00	7.07	Average	HORIZONTAL

EUT: FR-7M3416  
 Manufacturer: ShenZhen Fiberroad Technology CO., Limit  
 Operating Condition: WAORKIING  
 Test Site: Chamber 2  
 Operator: WYC  
 Test Specification: DC12V  
 Comment: /

Data: 1752 File: E:\E3 TEST DATA\1g-6g scan.EM6 (1796)



Trace: (Discrete)


Mark	Frequency MHz	Level dBuV	Factor dB	Reading dBuV	Limit dB	Margin dB	Det.	Polarization
1	2000.00	50.68	-4.16	54.84	80.00	29.32	Peak	VERTICAL
2	2935.00	51.17	-1.05	52.22	80.00	28.83	Peak	VERTICAL
3	3060.00	52.63	-0.46	53.09	80.00	27.37	Peak	VERTICAL
4	3435.00	51.95	0.95	51.00	80.00	28.05	Peak	VERTICAL
5	3685.00	48.90	2.26	46.64	80.00	31.10	Peak	VERTICAL
6	4250.00	52.34	3.53	48.81	80.00	27.66	Peak	VERTICAL
7	5000.00	59.89	5.43	54.46	80.00	20.11	Peak	VERTICAL

EUT: FR-7M3416  
 Manufacturer: ShenZhen Fiberroad Technology CO., Limit  
 Operating Condition: WAORKING  
 Test Site: Chamber 2  
 Operator: WYC  
 Test Specification: DC12V  
 Comment: /

Data: 1753

File: E:\E3 TEST DATA\1g-6g scan.EM6 (1796)


Date: 2019-03-15 Time: 09:23:04




Trace: (Discrete)

Mark	Frequency MHz	Level dBuV	Factor dB	Reading dBuV	Limit dB	Margin dB	Det.	Polarization
1	2000.00	44.94	-4.16	49.10	60.00	15.06	Average	VERTICAL
2	2935.00	44.81	-1.05	45.86	60.00	15.19	Average	VERTICAL
3	3435.00	47.09	0.95	46.14	60.00	12.91	Average	VERTICAL
4	3685.00	43.88	2.26	41.62	60.00	16.12	Average	VERTICAL
5	4250.00	45.74	3.53	42.21	60.00	14.26	Average	VERTICAL
6	5000.00	55.67	5.43	50.24	60.00	4.33	Average	VERTICAL



### 5. Test Setup Photos of the EUT









## 6. Photos of the EUT














.....End of Report.....